
Stormwater pond management system

The proposed Auckland Regional Landfill will be constructed

with a best practice stormwater pond management system to mitigate potential environmental effects and monitor water quality leaving the site.



This diagram is illustrative and is typical of a Class 1 landfill stormwater pond management system.

Drainage Bench

Reduces erosion on the landfill.

Primary Sedimentation Pond

Starts the process of removing sediment from the stormwater.

Series of Ponds

Retains and removes silt from the stormwater.

Settlement Pond

Manages flood peaks.

Discharge Control Valve

Controls the water level in the settlement pond.

Emergency Spillway

Safely allows for any extreme rain events.

Wetland Pond and Reed Beds

Final step in the process of filtering the stormwater.

Telemetry Monitoring System

Monitors stormwater discharge.

Discharge Point

Releases stormwater into the streams.



For updates about the proposed Auckland Regional Landfill visit wastemanagement.co.nz/arl

Questions? Call 0800 927 837 or email arl@wastemanagement.co.nz

7